

# PROCESSING ODS MODIFIED IN625 USING SELECTIVE LASER MELTING

A.B. Spierings<sup>1</sup>, T. Bauer<sup>1</sup>, K. Dawson<sup>2</sup>, A. Colella<sup>3</sup>, K. Wegener<sup>4</sup>

<sup>1</sup> Institute for rapid product development, Inspire AG, St.Gallen, Switzerland

<sup>2</sup> Centre for Materials and Structures, School of Engineering, University of Liverpool,  
Liverpool UK

<sup>3</sup> MBN nanomaterialia s.p.a, 31050 Vascon di Carbonera, Italy

<sup>4</sup> Institute of machine tools and manufacturing, Inspire AG, Tannenstrasse 3, 8092 Zurich,  
Switzerland

## Abstract

Increasing the operating temperatures of power plant turbine generators is a universal method to increase the efficiency of steam and gas turbines. However, operating a plant at higher temperatures poses extreme challenges to the materials used, especially regarding oxidation, creep, thermal fatigue- and stress-corrosion cracking. The EU-OXIGEN project addresses these issues by the development of novel processing routes for ODS-modified materials, as this class of materials offers exceptionally high temperature strength, oxidation and corrosion resistance at temperatures exceeding 900°C. Additive manufacturing processes such as Selective Laser Melting are considered to enable their successful processing. First results on density of SLM-processed, mechanically alloyed ODS-modified Inconel-625 superalloy powders, are presented and compared to the processing conditions and results of gas atomized conventional Inconel-625 powders.

Keywords: Selective Laser Melting, Additive manufacturing, ODS materials, Microstructure

---

## Introduction

Additive Manufacturing (AM) Technologies cover a wide range of comparably new production processes, where the parts to be built are manufactured layer by layer [13]. Thereby, the CAD file of a part to be built is sliced into thin layers with a typical thickness between 20µm and 200µm, depending on the specific process and the processing conditions. The raw material is then selectively consolidated within the cross-sections of the part at a specific height. Industrially relevant processes for the production of metallic components include Selective Laser Melting (SLM) and Layer Metal Deposition (LMD), where the energy required to melt a powdered metal material is delivered by a Laser beam. Due to the layer-wise build process, AM processes allow the manufacturing of highly complex shaped parts, which can significantly improve their performance [14] e.g. in terms of lightweight [25], functional [25], and structural optimization and thermal behaviour [10, 19, 23]. As a consequence Additive Manufacturing gains in importance in many industrial fields.

In SLM thin layers of a powdered raw material are deposited, and the energy beam is used to selectively scan the powder surface with the corresponding cross-sections. This leads to full melting of the powder particles exposed to the scanning laser spot and to selectively consolidate the powder material, reaching almost 100% material density [24, 33]. SLM processed materials typically offer properties quite comparable to the properties of conventional bulk materials [15, 28, 32]. There is a wide range of processable standard metal materials available: From stainless and hot-work steel [4, 24], Aluminium [5, 7, 8], Titanium [21] and Ni-based materials [20, 22] are typical metal classes. However, the SLM-process is a master forming process, implying that

the final material together with its incorporated properties are generated by the manufacturing process itself. This opens up new opportunities for the development of materials specific applications and sectors. An example are metal-diamond composites, as proposed by Spierings [26], where the diamond particles only can survive due to the very short laser-material interaction time, combined with a very high cooling rate of the melt pool. This basic concept can also be adapted to other classes of materials, such as Oxide Dispersion Strengthened (ODS) materials.

### ODS alloys

ODS alloys are an established class of materials that offer exceptional high temperature strength, oxidation and corrosion resistance at high temperatures exceeding 1000°C, along with outstanding resistance to radiation damage. ODS alloys contain transition metal oxides (usually yttrium based), forming fine dispersed particles in the metallic matrix. These particles hinder the movement of dislocations, thereby improving related material properties.

The history of ODS dates back decades. In the 1960's, Prof. N.G Grant of MIT studied two dispersion strengthening processes involving powder blends of oxides with copper and internal oxidation of copper and nickel alloys, finding dramatically improved high temperature strength. Further research was undertaken by Sadry, Alexander and Weeks et al. from the Technical Research Associates from NASA. They developed in the '80s techniques for producing castable ODS metals. However, one problem was that the alloys could not be welded nor was the solidification rate sufficiently high enough.

Nevertheless, such alloys are envisioned to be used in a number of future fossil energy and nuclear power applications [9], in order to improve their cycle efficiency by increasing the operating temperature of the turbine generator. Today, the inlet and exhaust temperatures of gas turbines are approximately 1500°C and 600°C, respectively, but will increase in the long term with exhaust temperatures exceeding 650°C. Operating a plant at such elevated temperature poses extreme challenges to the materials used; in particular, creep, thermal fatigue cracking and stress corrosion cracking are of major concern. However, while the fundamental material properties are expected to be well suited to turbine applications, the manufacture of components using ODS alloys are currently subject to a number of economic and technical barriers:

- Currently available mechanical alloying processing equipment used to produce ODS alloys are inefficient hence lead to high production cost.
- Oxide particles tend to coarsen when using conventional fusion (high heat input) and joining techniques, which can lead to reduced high temperature creep strength [16-18].
- ODS materials are difficult to repair for reasons given above.
- They are difficult to manufacture with traditional machining techniques (drilling, milling, grinding) due to their superior properties.
- Optimisation of high temperature creep strength in an ODS material requires recrystallization which produces coarse, usually high anisotropic grain structure.
- Coarse grained ODS alloys can give significant component to component variability in creep life. Moreover, these alloys tend to be creep brittle (e.g. <1% creep elongation to failure), so there can be little warning of imminent failure using time averaging approaches, increasing the risk of unplanned downtime.

Using the SLM process therefore opens up an alternative way towards manufacturing structurally optimised components out of ODS alloys, as the process-specific advantages such as short melt-pool lifetime and high cooling rate will favour superior ODS material properties by maintaining fine dispersed and homogeneous ODS particle distribution in the alloy matrix. The basic concept was already investigated by Walker [31] and Boegelein [6] for the Fe-based ODS alloy PM-1000 manufactured by Plansee. Boegelein concluded that a "*fine dispersion of*

*precipitates was retained in the SLM builds, and findings suggest that a certain amount of Y is probably still in atomic solution in the as-grown condition and forms new small nanoscopic dispersoids during annealing, which lead to enhanced strengthening”.*

The EU-OXIGEN project aims at the development of ODS modified super alloy powders and manufacturing routes for turbine applications. The current paper presents first results on SLM-processed conventional IN625 and a corresponding ODS modified alloy variant. The preliminary results show that there are many challenges to be addressed in order to reach high-density SLM parts.

## **Materials and Methods**

### Materials

In order to build a comparison basis, a standard IN625 powder material with a particle size distribution suitable for additive manufacturing was used. The alloy composition is shown in Table 1.

Table 1: Measured alloy composition of IN-625 powder

Element	Ni	Cr	Mo	Nb	Fe	Si	C	O	other
wt (%)	bal.	20.83	9.10	3.64	3.60	0.10	0.02	0.013	0.17

This powder raw material was also used to process an Yttrium oxide (ODS-) alloy variant, using High Energy Ball Milling (HEBM) techniques. Therewith, a material composition of  $99 \pm 1$ wt% of IN625 and 0–2 wt% of nano-yttrium oxide was achieved, named IN625-ODS.

### HEBM processing

A High Energy Ball Milling (HEBM) processing route, as described by Suryanarayana [30], has been specifically developed by MBN using a proprietary production plant for the manufacture of IN625-ODS powder for additive manufacturing. The challenge of milling IN625 base materials is closely related to the tendency of the powder particles of cold welding together during the process. This phenomenon might be prevented by an efficient dispersion of Yttria nanoparticles in the IN625 matrix, and modifying the HEBM processing parameters allows the balancing of the impact energy and therefore the fracturing behaviour and welding mechanisms of the particles. This results in improved dispersion homogeneity, and process yield of particle fractions suitable for SLM (Figure 1). Powder post-processing can be applied to increase this yield for suitable particle morphologies. HEBM processing and post-processing was performed in an inert atmosphere, minimizing the uptake of contaminants – mainly Oxygen and Nitrogen.

### SLM Machine and processing parameters

The materials have been processed by SLM using a ConceptLaser machine type M2. The machine is equipped with a 200W fibre laser with measured wavelength of 1071nm, operated in cw-mode. The scan strategy used to produce the  $10 \times 10 \times 10 \text{ mm}^3$  (IN625) and the  $8 \times 8 \times 3 \text{ mm}^3$  (IN625-ODS) test samples, respectively, is a meander-like scan strategy where the scan direction is turned by  $90^\circ$  for each layer, corresponding to the standard scan strategy used on ConceptLaser machines.

Table 2: A range of SLM processing parameter were applied for IN625 and IN625-ODS

	Layer thickness $t$ ( $\mu\text{m}$ )	Scan speed $v_s$ ( $\text{mm/s}$ ) *	Hatch distance $d$ ( $\mu\text{m}$ ) *	Energy level $E_L$ ( $\text{J}/\text{mm}^3$ )
IN625 / IN625-ODS	30	$v_1 - v_2$	$d_1 - d_2$	$E_1 - E_3 \approx 3.5 \times E_1$

\*No specific processing parameters are shown here.

### Powder particle size distribution

The PowderShape™ system analyses optically several thousand single powder particles (typically > 10'000) with an appropriate filtering mask, making sure that single particles are analyzed and no agglomerates of particles. According to Dvorak [11] the method delivers comparable results as laser scattering methods. For atomized powders, such as IN625, the filtering mask selects particles with a diameter between 4µm and 75µm. For milled powders, the filtering range was increased to 120µm as such particles are typically somewhat bigger, and more irregular in their shape. A particle diameter is considered as the diameter of a coextensive circle diameter.

### Measurement of mechanical properties

Mechanical material properties are measured on horizontally and vertically built and post-processed (drilled) test samples in the heat treated condition, according to EN-10002/ ISO-6892. The applied heat treatment follows the recommendation of AMS-2774 (1'038°C for 1h) [1]. A Walter&Bai tensile testing machine type LFV-25, equipped with clip gauges type MFA 25 / 12 is used. The sample diameter in the gauge section was 5mm.

### Sample Characterization

The SLM processed samples were analysed with regard to their material density using optical microscopy on polished samples and the Archimedes methods, as described in more detail by Spierings [27]. The microstructures of polished and etched (Kallings no.2) specimens were analysed using both optical and electron microscopy techniques. Furthermore, transmission electron microscopy (TEM) technologies were used to characterize IN625-ODS samples to get insight into material microstructure, and especially into ODS particles and precipitates.

Thin lamellae TEM specimens were produced in a dual beam FEI Helios 600i Focussed Ion Beam (FIB) instrument using the lift out method [12]. TEM analysis was performed using a 200kV JEOL 2100FCS microscope fitted with a windowless EDAX energy dispersive x-ray detector.

## Results and Discussion

### Powder raw material

The particle size distributions of the gas atomized IN625 is significantly different to the HEBM-processed IN625-ODS powder. The IN625 powder particles are distributed with a median value of 24µm, whereas the median of the ODS powder particles is about 17µm. However, the corresponding volume-based D<sub>10</sub>, D<sub>50</sub>, and D<sub>90</sub> values were comparable, with 22µm, 35µm and 51µm for IN625 and 22µm, 41µm and 58µm for IN625-ODS, respectively. The particle size distribution of IN625-ODS powders could be described by a Log-Normal distribution, whereas the IN625 powder shows more a bi-modal distribution with a small amount of fine particles in the range up to ≈15µm, as shown in Figure 1.




Figure 1: Particle size distribution of the IN625- (left) and IN625-ODS (right) powder

Furthermore, the powder can be distinguished in more detail using the Ellipticity  $E$  as the ratio of the major to the minor axis of a coextensive ellipse for each particle. The IN625 particles are more spherical with  $E = 1.25 \pm 0.26$ , whereas the IN625-ODS particles are more elliptical ( $E = 1.50 \pm 0.37$ ) aligned with a higher shape variation and a more irregular particle surface, as shown in Figure 2 (middle and right).




Figure 2: Powder particles for IN625- (left) and IN625-ODS powder (middle and right)

Both powders displayed good flowability with regard to the requirements for SLM, as described in Spierings et.al [29].

### SLM processed material density

Figure 3 shows the material density reached after SLM-processing of the powders according to the processing parameter ranges given in Table 2. It was clear that the powders – although similar in composition – behaved significantly different. As expected, the gas atomized IN625 powder reaches a very good material density of  $> 99.5\%$  after having reached a certain critical volume energy  $E_L$ , which is calculated as 
$$E_L = \frac{P}{v_s \cdot t \cdot d} \quad (1)$$




Figure 3: Left: Material density of SLM-processed IN625 and IN625-ODS over volume energy density between  $E_1$  and  $E_3$ ; SLM IN625-ODS samples built on a steel base plate (right).

In contrast, the ODS variant does not show a stable and wide processing window. A comparable density value can only be reached for a significant higher energy input of  $E_L$ , which is roughly double the value for the atomized IN625. Micro-graphical analysis show an increasing microporosity at lower  $E_L$ -levels (Figure 4). This correlates well with density behaviour as shown in Figure 3. In contrast, the IN625 microstructure is very homogeneous, without any cracks or bigger pores inside the consolidated material (Figure 4 right), reflecting the stable and wide processing window shown in Figure 3.




Figure 4: Micrographs for ODS-samples (left, middle) and etched IN625 sample (right)

Reasons for these differences are expected to be the fact that the powder layer density of milled powders will be significantly lower, due to the irregular particle shape and surface. In addition, the resulting microstructure with oxide particles / precipitates is leading to a different material morphology, where even the precipitates are expected to be porous.

### Mechanical properties of SLM-IN625

In order to build a comparison basis, heat treated SLM-processed IN625 material was tested at room temperature so far for its static mechanical properties. Table 3 gives an overview on current mechanical properties.


Table 3: Static mechanical properties of heat treated SLM-IN625 at room temperature

Orientation	Vertical	Horizontal	Anisotropy
Yield Strength (MPa)	$579 \pm 5$	$734 \pm 3$	-21 %
Ultimate Tensile Strength (MPa)	$888 \pm 6$	$1036 \pm 3$	-14%
Young's Modulus (GPa)	$159 \pm 5$	$200 \pm 3$	-20%
Elongation at break (%)	$40 \pm 1$	$36 \pm 0.3$	+11%

The very low standard deviation of 5 samples per orientation reflects the good processing window, and the comparably low level of defects. The measured properties outperform the requirements given by ASTM-3056 [3] significantly, and reach almost the requirements given in the ASM Handbook [2], where the required Ultimate Strength is just the mean value of the measured properties. However, an exception is the Elongation at break where 50% would be required. This indicates a somewhat higher brittleness compared to conventional cast material.

### Microstructural analysis

For the ODS-modified IN625 material, all samples in an Energy level range  $E_L$  between  $E_1$  and  $2 \times E_1$  show a similar distribution of Nb-Cr-Y oxides in the size range of 30nm to about 500nm, as shown in Figure 5 (left pictures). This is somewhat in contrast to findings of Boegelein [6] for Fe-based PM2000, where a comparably fine dispersion of nano-sized precipitates was found after annealing. It is expected that this was due to the retention of Y in solid solution in the as-built condition as a result of the very high cooling rate, which prevented formation and growth of precipitates.






Figure 5: Microstructural analysis of IN625-ODS. Bottom: Energy level  $E_1$ , Top: Energy level  $E_2 \approx 2 \times E_1$

In addition, grain boundary cracks in parallel to the build orientation (z-direction) are visible, with an indication of increasing crack length with increasing scan velocity (and a corresponding higher cooling rate). This might also be affected by a weakening effect of the coarse precipitates, in combination with internal stresses in the material, as in pure IN625 such cracks could not be found. The analysis of Nb-Cr-Y-Al oxide precipitates in the IN625-ODS material shows a complex nature of these particles (Figure 6).




Figure 6: Top: Microstructural analysis of precipitates in IN625-ODS ( $E_L = E_1$ ), showing mainly signals of Nb, Cr, Y, Al, and O.

The precipitates contained some internal porosity, which might have contributed to the overall porosity of the IN625-ODS material, at least to some degree. The precipitates, in general, were polycrystalline, with unidentified crystal structure, as the fast Fourier transforms (FFT) of the TEM lattice images (Figure 7) were ambiguous.




Figure 7: Microstructural analysis precipitates in IN625-ODS.  $E_L = E_1$ .

## Conclusions

The results so far indicate that it is possible to additively manufacture structures from mechanically alloyed powders with a more irregular particle shape. However, the processing window can be influenced significantly, as a higher energy input can be required to reach full material density. In any case, the quality of the processed IN625-ODS material does not yet fulfil the requirements in terms of a stable and wide processing window, and in terms of the resulting material micro structure.

Several aspects have to be considered therefore, aiming principally on a SLM-processing window where an as low energy input as possible is required. Achieving this would better allow to maintain Y in solid solution in the as-processed condition. A supplementary strategy could be the definition of a SLM processing window, where the material density reaches values in the range of about 97%, with a corresponding lower laser scan velocity. An additional HIP procedure could then be applied in order to increase material density, and to start formation of homogeneously distributed of fine precipitates.

This can be achieved by optimizing the particle size distribution, and particle morphology. It is expected that the very wide processing window for IN625 is also a result of an optimal particle size distribution, resulting in a higher powder layer density compared to IN625-ODS. Furthermore, the processing route of mechanical alloying of IN625 with Y should be investigated.

## Outlook

Further SLM-processing trials with other, improved IN625-ODS powders will follow. Appropriate microstructural investigations are needed to characterize in more detail the formation of precipitates. Finally, the mechanical material properties have to be measured, in combination with material oxidation resistance. These results have to be compared to the behaviour of conventional IN625, where comparably good properties can be achieved using Selective Laser Melting.

## Acknowledgements

The work was funded by European Commission within the FP7-Project OXIGEN, Grant No. NMP3-SL-2011-310279.

## Literature

1. AMS2774, *AEROSPACE MATERIAL SPECIFICATION: Heat Treatment Wrought Nickel Alloy and Cobalt Alloy Parts*. ASM International, Vol. 10, 31. 1995, rev. D
2. ASM\_Speciality\_Handbook, *Nickel, Cobalt and their alloys*. ASM International, Vol. 10, 417. 2000
3. ASTM\_International, *ASTM F3056-14e1: Standard Specification for Additive Manufacturing Nickel Alloy (UNS N06625) with Powder Bed Fusion*. ASTM\_International: West Conshohocken, PA. 2014.
4. Averyanova, M. and P. Bertrand. *Direct Manufacturing of dense parts from martensitic precipitation hardening steel gas atomized powder by Selective Laser Melting (SLM) technology*. in *Int. Conference on Advanced Research in Virtual and Rapid Prototyping*. Leiria, Portugal: 6-10 October 2009, CRC Press / Balkema. 343-348, 2010.
5. Berkau, A. *Einsatzmöglichkeiten des Strahlschmelzens zur Herstellung von Bauteilen aus Aluminium*. in *16. Anwenderforum Rapid Product Development*. Stuttgart: 5. oktober 2011, citim GmbH. 2011.
6. Boegelein, T., et al., *Mechanical response and deformation mechanisms of ferritic oxide dispersion strengthened steel structures produced by selective laser melting*. 2015, Acta Materialia, **87**(0): p. 201-215.
7. Brandl, E., U. Heckenberger, V. Holzinger, and D. Buchbinder, *Additive manufactured AlSi10Mg samples using Selective Laser Melting (SLM): Microstructure, high cycle fatigue*,

- and fracture behavior. 2012, *Materials & Design*, **34**(0): p. 159-169.
8. Buchbinder, D., et al., *High Power Selective Laser Melting (HP SLM) of Aluminum Parts*. 2011, *Physics Procedia*, **12, Part A**(0): p. 271-278.
  9. Chawla, V., S. Prakash, and B.S. Sidhu, *State of the art: Applications of Mechanically Alloyed Nanomaterials - A Review*. 2007, *Materials and Manufacturing Processes*, **22**(4): p. 469-473.
  10. Dimitrov, D., A. Moammer, and M. Mabogo. *Thermal Management of Moulds and Dies – State of the Art and Future Perspectives. in 3rd International Conference on Polymers and Mould Innovations PMI 2008*. Gent, Belgium: 17-19 September 2008. 355-360, 2008.
  11. Dvorak, M., H.G. Schmid, F. Fischer, and F. Barchfeld. *Fast Quality Control of Spray Powders / Schnelle Pulverkorngrößenbestimmung zur Qualitätskontrolle. in Int. Thermal Spray Conf ITSC*. Essen. 2002.
  12. Giannuzzi, L.A. and F.A. Stevie, *A review of focused ion beam milling techniques for TEM specimen preparation*. 1999, *Micron*, **30**(3): p. 197-204.
  13. ISO/DIS\_17296-1, *Additive manufacturing - General principles - Part 1: Terminology*. 2014. p. 21.
  14. Klahn, C., B. Leutenecker, and M. Meboldt, *Design for Additive Manufacturing – Supporting the Substitution of Components in Series Products*. 2014, *Procedia CIRP*, **21**(0): p. 138-143.
  15. Kruth, J.P., B. Vandenbroucke, J. Van Vaerenbergh, and P. Mercelis. *Benchmarking of different SLS / SLM Processes as Rapid Manufacturing Techniques. in Int. Conf. Polymers & Moulds Innovations (PMI)*. Gent, Belgium: April 20-23. 1-7, 2005.
  16. Lemmen, H.J.K., K.J. Sudmeijer, I.M. Richardson, and S. Van der Zwaag, *Laser beam welding of an Oxide Dispersion Strengthened super alloy*. 2007, *Journal of Materials Science*, **42**(13): p. 5286-5295.
  17. Lindau, R., et al., *Mechanical and microstructural characterization of electron beam welded reduced activation oxide dispersion strengthened – Eurofer steel*. 2011, *Journal of Nuclear Materials*, **416**(1–2): p. 22-29.
  18. Molian, P.A., Y.M. Yang, and P.C. Patnaik, *Laser welding of oxide dispersion-strengthened alloy MA754*. 1992, *Journal of Materials Science*, **27**(10): p. 2687-2694.
  19. Mueller, B., et al., *Added value in tooling for sheet metal forming through Additive Manufacturing, in International Conference on Competitive Manufacturing: Stellenbosch, SA*. 2013.
  20. Mumtaz, K.A., P. Erasenthiran, and N. Hopkinson, *High density selective laser melting of Waspaloy®*. 2008, *Journal of Materials Processing Technology*, **195**(1-3): p. 77-87.
  21. Murr, L.E., et al., *Microstructure and mechanical behavior of Ti-6Al-4V produced by rapid-layer manufacturing, for biomedical applications*. 2009, *Journal of the Mechanical Behavior of Biomedical Materials*, **2**(1): p. 20-32.
  22. Rickenbacher, L., T. Etter, S. Hövel, and K. Wegener, *High temperature material properties of IN738LC processed by Selective Laser Melting (SLM) technology*. 2013, *Rapid Prototyping Journal*, **19**(4): p. 282 - 290.
  23. Sagert, D. and I. Scholl, *Vom Versuch zur Standardtechnologie - LaserCusing-Werkzeugkerne aus Warmarbeitsstahl reduzieren Ausschussrate, in Giesserei-Erfahrungsaustausch*. 2009. p. 12-15.
  24. Spierings, A.B., N. Herres, and G. Levy, *Influence of the particle size distribution on surface quality and mechanical properties in additive manufactured stainless steel parts*. 2011, *Rapid Prototyping Journal*, **17**(3): p. 195 - 202.
  25. Spierings, A.B., L. Labhart, and K. Wegener. *Production of functional parts using SLM – Opportunities and limitations. in 5th International Conference on Advanced Research in Virtual and Rapid Prototyping (VRAP)*. Leiria, Portugal: CRC press, Taylor & Francis. 785-790, 2012.
  26. Spierings, A.B., C. Leinenbach, C. Kenel, and K. Wegener, *PROCESSING OF METAL-DIAMOND-COMPOSITES USING SELECTIVE LASER MELTING, in Proceedings of the Annual International Solid Freeform Fabrication Symposium*. D.L. Bourell, Editor: Austin, Texas. 2014.
  27. Spierings, A.B., M. Schneider, and R. Eggenberger, *Comparison of Density Measurement Techniques for Additive Manufactured metallic Parts*. 2011, *Rapid Prototyping Journal*, **17**(5):

- p. 380-386.
28. Spierings, A.B., M. Schoepf, R. Kiesel, and K. Wegener, *Optimization of SLM productivity by aligning 17-4PH material properties on part requirements*. 2014, *Rapid Prototyping Journal*, **20**(6): p. 444-448.
  29. Spierings, A.B., M. Voegtlin, T. Bauer, and K. Wegener, *Powder flowability characterization methodology for powder-bed based metal additive manufacturing*. 2015, *Progress in Additive Manufacturing*, **submitted**.
  30. Suryanarayana, C., *Mechanical alloying and milling*. 2001, *Progress in Materials Science*, **46**(1-2): p. 1-184.
  31. Walker, J.C., K.M. Berggren, A.R. Jones, and C.J. Sutcliffe, *Fabrication of Fe--Cr--Al Oxide Dispersion Strengthened PM2000 Alloy Using Selective Laser Melting*. 2009, *Advanced Engineering Materials*, **11**(7): p. 541-546.
  32. Wang, F., *Mechanical property study on rapid additive layer manufacture Hastelloy® X alloy by selective laser melting technology*. 2012, *The International Journal of Advanced Manufacturing Technology*, **58**(5-8): p. 545-551.
  33. Yasa, E., J. Deckers, and J.P. Kruth, *The investigation of the influence of laser re-melting on density, surface quality and microstructure of Selective Laser Melting parts*. 2011, *Rapid Prototyping Journal*, **17**(5).